

Schedule of Infiltration and Inflow (I&I) – Contribution Removal Values By  
Source and Fee Schedule

I&I Mitigation Method	Severity	I&I Credit (gpm)*	Availability
<b>Manholes</b>			
Surface Water Entering MH/Inflow Protector Installed Or Low Lying/Buried MH Raised		4	No
Frame, Frame to Cone, Cone to Barrel, or Barrel Joint leaks	Severe	5	No
	Moderate	3	No
	Slight	1	No
Frame,Cone, Barrel leaks (not along joints)	Severe	2	No
	Moderate	1	No
	Slight	0.5	No
Expose frame and cone in ditch (Exterior)	Severe	15	No
	Moderate	10	No
	Slight	5	No
Manhole replacement		15	No
Cracks in the concrete or paved surface area surrounding a manhole with leaks in frame and core		5	No
			No
			No
<b>Pipe Segments</b>			
Joint infiltration or cracked pipe		1	No
Pipe broken		2	No
Cured in Place Piping (CIPP) or Pipe Replacement per 100 feet	6" pipe	7	No
	<b>8" pipe</b>	<b>8</b>	<b>Yes (\$250/gpm)</b>
	10" pipe	9	No
	12" pipe	10	No
	15" pipe	13	No
	18" pipe	15	No
	21" pipe	17	No
24" pipe	18	No	
<b>Private Sources</b>			
Property lawn vents and clean outs	Missing	0.1	No
	Low Lying Vent	1	No
	Loose/Broken Riser	10	No
Downspout		5	No
Sump pump		1	No
<b>Deficient residential lateral building foundation to connection at right of way</b>	<b>Case -specific, no general classification</b>	<b>8</b>	<b>By approval of Town Engineer</b>
<b>Leaking lateral at the connection to the main (main to right of way)</b>		<b>12</b>	<b>Yes (\$250/gpm)</b>

\* Source Erie County Division of Sewerage Management, General Infiltration and Inflow (I&I) - Contribution Removals by Source, with exception of leaking lateral at the connection to the main and deficient residential lateral building foundation to connection at right of way