

SUMMARY OF ANNUAL BIDS

Bid Tabulation for March, 2021

OMNI-RUPTER SWITCH (2) bidders:

Awarded to Stuart C. Irby

| | <u>Quantity</u> | <u>Price</u> |
|--|-----------------|-----------------|
| New and un-used OMNI-RUPTER SWITCH outdoor distribution 14.4 KV through 34.5 KV w/6 #4738 connectors | <u>3</u> | \$3,450.00 each |

S&C Catalog Number: 147412R4-H-P1/ED-700R4

| <u>Quantity</u> | <u>Price</u> |
|-----------------|------------------|
| <u>2</u> | \$11,560.00 each |

Alduti-Rupter Switch

Outdoor distribution – 3 pole side break integer style with porcelain station post insulators and an insulated base, upright clockwise-opening mounting configuration, ED-637R3 mounting arrangement (rotating) 34.5 KV nominal, 38 KV maximum, 200KV BIL, 600 amperes RMS continuous, 600 amperes RMS

Interrupting, 40,000 amperes RMS momentary (Asymmetrical), less crossarm brace or crossarm provisions, A2 - Mounting provisions for Six (6) surge arresters per switch

S1 - One (1) 2 5/8-inch diameter tubular fiberglass insulating section in vertical operating shaft

S&C Catalog Number: 137394R1-A2/ED-637R3-S1

| <u>Quantity</u> | <u>Price</u> |
|-----------------|------------------|
| <u>1</u> | \$13,623.00 each |

Alduti-Rupter Switch

Outdoor distribution, three pole vertical break tyle, upright mounting style ED-xxxx (Erection drawing will need to be determined prior to ordering), 34.5 KV nominal, 38 KV Maximum, 200 KV BIL, 600 Amperes RMS continuous, 600 amperes RMS interrupting, 40,00 amperes RMS momentary (asymmetrical), porcelain station post insulators, less connectors

S1 - 2 5/8-inch diameter tubular fiberglass insulating section in vertical operating shaft

S&C Catalog Number: 135774R3/ED-xxxxS17394R1-A2/ED-637R3-S1

SPOOLED WIRE (3 bidders):

Awarded to Scott Electric

BIDDER'S PROPOSAL FORM

| | <u>Quantity on Reel</u> | <u>Price</u> |
|------------------------------------|-------------------------|--------------|
| # 2 Alv. Triplex (conch) | 1800' reel | \$1,150.20** |
| 1/0 Alv. Triplex (neritina) | 1200' reel | \$1,290.00** |
| 1/0 THHN (copper) | 500' reel | \$ 960.27** |
| 336.4 Poly (anona) | 2500 reel | \$2,587.50** |
| 1/0 Primary Cable | | |
| Prysmian Double Seal TM | 2500' reel | \$7,475.00** |
| cable x EPR | 175 mils | |
| 1/0 Awg AL 15 kv Ins. JKT | | |

{NO EXCEPTIONS}

** Due to the current volatility of the wire market, these prices are valid for today only and are subject to change to the current pricing, upon placing of an order. Everything except the 1/0 THHN: must be ordered in standard put-ups as indicated above, freight is allowed on orders in excess of 5000 pounds

TRANSFORMERS [2 bidders]:

Awarded to ERMCO c/o Delta-Wye Associates

| <u>KVA</u> | <u>TYPE</u> | <u>Price ea.</u> | <u>watts No-load Loss</u> | <u>watts Load Loss</u> |
|------------|-----------------|------------------|---------------------------|------------------------|
| 15 | CONV Pole-mount | \$816.00 | 47 | 211 |
| 15 | CONV Pole-mount | \$1,055.00 | 47 | 220 |
| 25 | CONV Pole-mount | \$945.00 | 61 | 349 |
| 25 | CSP Pole-mount | \$1,181.00 | 68 | 336 |
| 25 | Pad mount | \$1,500.00 | 68 | 318 |
| 37.5 | CONV Pole-mount | \$1,139.00 | 78 | 481 |
| 37.5 | CSP Pole-mount | \$1,446.00 | 78 | 505 |
| 50 | CONV Pole-mount | \$1,197.00 | 98 | 589 |
| 50 | CSP Pole-mount | \$1,514.00 | 98 | 632 |
| 50 | Pad mount | \$1,805.00 | 108 | 575 |
| 75 | CONV Pole-mount | \$1,835.00 | 146 | 742 |
| 75 | Pad mount | \$2,200.00 | 131 | 856 |
| 100 | Pad Mount | \$2,687.00 | 175 | 996 |

WOOD UTILITY POLES (4 BIDDERS):

Awarded to Koppers

| <u>Class</u> | <u>length</u> | <u>Spec.</u> | <u>Price ea.</u> | | |
|--------------|---------------|--------------|------------------|-----------|--|
| 2 | 30' | CCA-CE | \$250.00 | 2-3 weeks | |
| 3 | 30' | CCA-CE | \$210.00 | 2-3 weeks | |
| 2 | 35' | CCA-CE | \$314.00 | 2-3 weeks | |
| 3 | 35' | CCA-CE | \$265.00 | 2-3 weeks | |
| 2 | 40' | CCA-CE | \$394.00 | 2-3 weeks | |
| 3 | 40' | CCA-CE | \$331.00 | 2-3 weeks | |
| 2 | 45' | CCA-CE | \$472.00 | 2-3 weeks | |
| 3 | 45' | CCA-CE | \$409.00 | 2-3 weeks | |
| 2 | 50' | CCA-CE | \$547.00 | 2-3 weeks | |
| 3 | 50' | CCA-CE | \$478.00 | 2-3 weeks | |
| 2 | 55' | CCA-CE | \$646.00 | 2-3 weeks | |
| 3 | 55' | CCA-CE | \$553.00 | 2-3 weeks | |
| x | x | | | | |